

Whitewashing & Painting work on MBA Lift Area, S-7 Class room, VC Camp office & residence in the J.C. Bose University of Science & technology.

| Sr. No | Item Name | Qty. | Unit | Basic Price in Rs. | Amount |
|--------|--|--------|------|--------------------|----------|
| 1. | Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work HSR 30.27.1 | 277.67 | Sqm | 41.97 | 11653.81 |
| 2. | Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. HSR 11.60 | 206.55 | Sqm | 58.94 | 12174.06 |
| 3. | Finishing walls with Acrylic Smooth exterior paint of required shade: Old work (One or more coat applied @ 0.90 litre/10 sqm). HSR 30.37.2 | 185.80 | Sqm | 40.19 | 7467.30 |
| 4. | Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade One or more coats on old work HSR 30.28.1 | 169.27 | Sqm | 38.40 | 6499.97 |
| | | | | Total | 37795.14 |
| | | | | % on HSR 2021 | |
| | | | | Total | |